

NOTES:

1. PLASTIC COVERS SHALL BE INSTALLED OVER STOCKPILES AS THEY ARE GENERATED THROUGHOUT THE PROJECT. COVERS SHALL PREVENT EROSION AND SEDIMENT TRANSFER PRIOR TO RAIN EVENTS.
2. SEAMS SHALL BE TAPED OR WEIGHTED DOWN THEIR ENTIRE LENGTH.
3. COMPOST FILTER SOCK SHALL BE INSTALLED TO RETAIN SEDIMENT RUNOFF.
4. STOCKPILE SLOPES SHALL NOT EXCEED 2:1.
5. OFF-SITE BORROW/FILL AREAS SHALL ALSO BE PROTECTED BY ADEQUATE SEDIMENT AND EROSION CONTROL BMPs. IF PART OF A JOB DISTURBING 1 ACRE OR GREATER THEIR LOCATION SHALL BE NOTED WITHIN THE SWPPP.
6. ADHERE TO COMPOST FILTER SOCK STANDARDS FOR MAINTENANCE.
7. STOCKPILE BMPs MAY BE REMOVED AFTER AREA IS STABILIZED

